OFFICE OF THE SPECIAL DUTY OFFICER, DASARA FESTIVITIES.

Tender Notice No. O. 664, dated 8—9th September 1931.

Notice is hereby given that sealed tenders will be received by 3 P.M. at the Office of the Special Duty Officer, Dasara Festivities, General and Revenue Secretariat, Bangalore, up to 25th September 1931, for constructing about half a dozen temporary latrines, about ten motor sheds and about 20 to 30 temporary sheds at Mysore to serve as kitchen and bath rooms for the use of Guests and Representative Assembly Members to be accommodated in several Government buildings. The specifications of the sheds and latrines are given below. The work should be completed by the 15th October 1931.

2. Each tender must be accompanied by a deposit of Rs. 50 in cash or Government Promissory Notes as earnest money, and be superscribed "Tender for construction of temporary sheds at Mysore," in default of which, tenders will be rejected.

3. The final acceptance of any tender will rest in the Special Duty Officer, Dasara Festivities, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

4. Within three days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond with a security deposit of Rs. 100 in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

5. The name of the sucessful competitor, whose tender has been accepted will be posted on the Notice Board in the Special Duty Office, at the Indian Guests' Quarters, Mysore, in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

6. On acceptance of any one of the tenders, the earnest money on rejected tenders will be returned.

Specifications.

1. Each kitchen and bath shed to measure about 20′ x 10′ divided into three compartments made out of thatti mat walls and doors and thatched roof with grass on the top. Each shed to consist of one kitchen cistern and one bath cistern and one big oven and two small ovens. Ground to be cleaned and to be washed with cow-dung and the drainage around the shed arranged for.

2. Each motor shed to measure about 18′ x 12′ made out of thatti mat walls and doors and thatched roof with grass on the top. Ground to be cleared and scraped and the drainage around the shed arranged for.

3. Each latrine to measure about 4′ x 5′ built of thatti mat walls and provided with a pit 3′ x 1′ x 1′. The ground to be cleaned and scraped.

4. The materials to be used may be taken back by the contractor after the occasion and the grounds levelled and made clean and tidy after removal.

K S RAMA IYER
Special Duty Officer.